



To Whom It May Concern:

The City of Sedona, Arizona is issuing **Addendum # 1** to the plans and specifications as originally issued at the time of solicitation for bids for the **Harmony-Windsong Phase IV Drainage Project**. For any bid to be considered responsible and responsive, receipt of this addendum must be acknowledged.

As specified in the Instructions to Bidders this Addendum upon issuance has become a part of the Contract Documents.

This Addendum contains 3 pages including this page, 0 changed bid sheets, and 4 plan sheets. Any changed bid sheets shall be used in lieu of the originally issued bid sheets in order to submit a responsive bid.

This Addendum changes the following:

- 1) **Technical Specifications, Section 2.2, Items of Work, Items 1 through 6, 8, and 9 – Storm Drain, add to the end of this section, “The dual 72” or 60” CMP storm drain lines shall have helical 3” x 1” corrugations, and shall be 10 gauge pipe.”**
- 2) **Technical Specifications, Section 2.2, Items of Work, Item 38 - Sawcut, Curb & Gutter, Grading, Core Drilling and Rip Rap, add to the end of this section, “This item is excluded from the base bid, and shall be bid as an additive alternative, as indicated on the bid schedule.”**
- 3) **Special Conditions, Section 9 – Stormwater Pollution Prevention Plan, add to the end of the 2nd paragraph, “...This bid item includes all provisions indicated on the cover sheet of the SWPPP provided in the plans, including but not limited to, seeding, erosion and sediment control, and related strategies and practices.”**
- 4) **Plans, Drawing P1, Sheet 6 of 12, for the cross section indicated near Sta. 45+15, the detail and page number indicated are incorrect. It should reference Detail 2, on Drawing C2.**
- 5) **Plans, Drawing C2, Sheet 2 of 12, for details 1 & 2, remove note indicating high survivability and low survivability filter fabric. In Technical Specifications, Section 2.2, Items of Work, Items 1 through 6, 8, and 9 – Storm Drain, revise the 11th paragraph to read, “All filter fabric shall be Contech C200 or equivalent for the following properties: Tensile Strength, Elongation @ Break, CBR Puncture, Trapezoidal Tear, Apparent Opening Size, Permittivity, Water Flow Rate, and UV Resistance @ 500 Hours.”**
- 6) **Special Conditions, Section 12 - Various Items of Work, edit the last sentence of the 3rd paragraph to read, “No separate payment shall be made trees, except for the trees indicated for removal under Bid Item 32 – Remove Exist Tree.”**
- 7) **Technical Specifications, Section 2.2, Items of Work, Item 44 – Clear and Grub, add to the end of this section, “This item shall include removal, haul off, and appropriate disposal of all miscellaneous debris not directly indicated on the plans, including but not limited to broken concrete, appliances, furniture, wire mesh, etc.**
- 8) **Technical Specifications, Section 2.2, Items of Work, Item 27 – Construction Coordination with Water Company and Dry Utility Companies, remove the last paragraph, and replace with the following, “Work in the vicinity of the**

underground dry utility lines shall be coordinated with the dry utility companies, at Moonglow Drive. This includes coordination with APS, CenturyLink, and SuddenLink. The existing dry utility lines on the south side of Moonglow shall be protected in place while work is conducted in this area. The power company will shut off power to the line during the work, and will re-establish power once the contractor has completed their work in the area.

- 9) Plans, Drawings P2 and P3, beginning at Sta. 50+13.00, the standard trench width shall be 16' as indicated on Detail 1 on Drawing C2, not the 18' width as illustrated on the plan view of Drawings P2 and P3.
- 10) Pre-Bid Meeting Sign-In Sheet. This form is attached for plan holders' information.

ACKNOWLEDGEMENT

I have received addendum # 1 for the **Harmony-Windsong Phase IV Drainage Project** as described above, and acknowledge it as part of the Contract Documents for the project.

Signature

Date

Print Business Name

Addendum # 1 issued by Charles Mosley, P.E. Director of Public Works/City Engineer, City of Sedona



Charles Mosley, P.E., Director of Public Works/City Engineer

8/30/13

Date

SIGN IN SHEET

Harmony-Windsong Phase IV Drainage Project
Pre-Bid Mtg 8/26/13

NAME	FIRM NAME	TEL. NO.	E-MAIL
Stephen Craver	COS	928-203-5059	scraver@sedona2.gov
Art Beckwith	SKL	928 282 1061	abeckwith@swigaz.com
Nyle R. Loren	SNOWWESTERS CONTRACTORS	520-684-8000	SWC@SNOWWESTERSCONTRACTORS.COM
Jerry Hine	BTF Contracting INC	623-582-1170	Estimating@BTFcontracting.com
Doug Hawkins	Tiffany Construction	928-204-9817	tiffany@sedona.net
Curt Potter	ADAMS Contracting	623-764-3972	ADAMS.CONTRACTING@ADL.COM
MIKE ATKIN	SDB, INC. (GEN. CONTR.)	928-779-4545	michael.atkin@sdb.com
JEFF CARMAN	ALLIANCE STREETWORKS	928-567-8096	BELLS.ALLIANCE@YAHOO.COM
Cecil Zuniga	Redpoint Contracting	602 792-0013	estimating@redpointcontracting.com
Manuel Pasillas	Standard Construction	623-583-9500	mpasillas@standardaz.com
J. Andy Dickey	CITY OF SEDONA	928-203-5039	adickey@sedonaaz.gov
MICK LITTLE	MCCOOLEY CONST.	928-289-9557	mccoley@sedonaaz.gov
ROBERT KING	NINYO AND MOORE	928-237-0194	RKING@NINYOANDMOORE.COM
JOHN BACIGALUPI	CONTECH ENGINEERED SOLUTIONS	602 377 5347	John6@contech-epi.com
MARK WATSON	THT Construction, Inc.	480-837-2192	Estimating@tthconstruction.com
Wyatt Orr	Earth Resources Corp	928-775-2795	Wyo5th@yahoo.com
Favis Brewer	Brewer Bros Cont.	928-300-4659	brewertravis@esedona.net
Garry Shurtz	RKSanders Inc	602 233 0808	garrys@rksandersinc.com
Tony Lago	EAGLE MOUNTAIN	928-526-7587	LAGRO@EMCAZ.COM

L:\HARMONY PHASE 4\Meetings\PREBID SIGN IN SHEET.xls\SIGN IN