

# CONSTRUCTION PLANS FOR THE POSSE GROUNDS PARK IMPROVEMENTS


**CITY OF SEDONA**

**MAYOR**  
ROB ADAMS

**CITY COUNCIL**  
JOHN MARTINEZ  
BARBARA LITRELL  
MARK DINUNZIO  
DAN MCILROY  
JESSICA WILLIAMSON  
MIKE WARD


**CITY MANAGER**  
TIM ERNSTER

**DIRECTOR OF PUBLIC WORKS**  
CHARLES MOSLEY, P.E.



VICINITY MAP

NO SCALE



102 ROADRUNNER DRIVE  
SEDONA, ARIZONA 86336

**BASIS OF BEARINGS AND COORDINATES**

LINEAR UNIT: INTERNATIONAL FOOT  
GEODEIC DATUM: NAD83 (NSRS 2007)  
VERTICAL DATUM: NAVD88 (SEE BELOW)  
SYSTEM: SHEPHARD-WESNITZER  
ZONE: SEDONA

PROJECTION: TRANSVERSE MERCATOR  
LATITUDE OF GRID ORIGIN: 34° 44' 00" N  
LONGITUDE OF CENTRAL MERIDIAN: 111° 48' 00" W  
NORTHING AT GRID ORIGIN: 0.00 FT  
EASTING AT CENTRAL MERIDIAN: 50,000.00 FT  
CENTRAL MERIDIAN SCALE FACTOR: 1.000206

ALL MEASURED DISTANCES AND BEARINGS SHOWN HEREON ARE GRID VALUES BASED ON THE PRECEDING PROJECTION DEFINITION. THE PROJECTION WAS DEFINED SUCH THAT GRID DISTANCES ARE EQUIVALENT TO "GROUND" DISTANCES IN THE PROJECT AREA.

THE BASIS OF BEARINGS IS TRUE GEODETIC NORTH. NOTE THAT THE MEASURED GRID BEARINGS SHOWN HEREON (OR IMPLIED BY GRID COORDINATES) DO NOT EQUAL GEODETIC BEARINGS DUE TO MERIDIAN CONVERGENCE.

ORTHOMETRIC HEIGHTS (ELEVATIONS) WERE TRANSFERRED TO THE SITE FROM NGS POINT 'VORTEX' (NGS PID AJ5637) USING GPS WITH NGS GEOID MODEL 'GEOID03'. ELEVATIONS SHOWN HEREON ARE REFERENCED THE PUBLISHED ELEVATION OF THIS STATION.

THE SURVEY WAS CONDUCTED USING GPS REFERENCED TO THE NATIONAL SPATIAL REFERENCE SYSTEM, 2007 READJUSTMENT. A PARTIAL LIST OF POINT COORDINATES FOR THIS SURVEY IS GIVEN BELOW (ADDITIONAL COORDINATES ARE AVAILABLE UPON REQUEST). LOCAL NETWORK ESTIMATES ARE GIVEN AT THE 95% CONFIDENCE LEVEL AND ARE BASED ON AN APPROPRIATELY CONSTRAINED LEAST-SQUARES ADJUSTMENT OF OVER-DETERMINED AND STATISTICALLY INDEPENDENT OBSERVATIONS.

POINT	LATITUDE	LONGITUDE	HT (FT)	NORTH (FT)	EAST (FT)	ELEV. (FT)	CODE
3003	34°52'10.24986"N	111°47'12.98735"W	4453.59	49575.59	53918.22	4533.61	NAIL 60D
3002	34°51'59.66570"N	111°47'18.22365"W	4409.03	48505.22	53481.93	4489.09	NAIL MAGNETIC
4001	34°52'07.03782"N	111°47'14.29101"W	4448.96	49250.76	53809.61	4528.98	NAIL 60D
4003	34°52'08.23393"N	111°47'14.03334"W	4451.63	49371.72	53831.07	4531.64	NAIL 60D

APPROVED: \_\_\_\_\_  
DESIGN ENGINEER

APPROVED: \_\_\_\_\_  
CITY ENGINEER

**SHEET INDEX**

SHT NO.	DWG NO.	DESCRIPTION
1	C1	COVER SHEET
2	C2	NOTES
3	C3	DETAILS
4	C4	DETAILS
5	C5	OVERALL SITE PLAN AND FIELD SURVEY CONTROL
6	C6	PARKING & SIDEWALK GRADING AND DRAINAGE PLAN
7	C7	PARKING AND SIDEWALK SURVEY CONTROL
8	S1	STORM WATER POLLUTION PREVENTION PLAN
9	S2	STORM WATER POLLUTION PREVENTION PLAN



REVISIONS			
NO.	DESCRIPTION	DATE	BY




75 Kollof Place  
Sedona, AZ 86336  
928.282.1061  
928.282.2058 fax  
www.swiaz.com

JOB NO:	11311
DATE:	NOV 12
SCALE:	AS SHOWN
DRAWN:	MWJ
DESIGN:	DMM
CHECKED:	AHB

POSSE GROUNDS PARK IMPROVEMENTS

SEDONA  
ARIZONA

COVER SHEET












DRAWING NO.

C1

SHT NO. OF  
1 9



PLOTTED: Nov 07, 2012--11:15am










**NOTES**

1. ALL CONCRETE SHALL BE CLASS "C" PER SECT. 725.
2. FITTINGS NOT SPECIFICALLY DETAILED SHALL BE HEAVY DUTY DESIGN.
3. STRAIN POSTS SHALL BE SPACED AT 500" MAXIMUM SPACING.
4. BOTH CORNER AND STRAIN POSTS SHALL HAVE STRAIN PANELS.
5. ALL POSTS SHALL BE CAPPED.
6. MEMBER SIZES SHALL BE THE FOLLOWING:

MEMBER	AISC SIZE	OUTSIDE DIA.
CORNER POST	2-1/2"	2.875"
LINE POST	1-1/2"	1.900"
STRAIN POST	1-1/2"	1.900"
BRACE	1-1/4"	1.666"
STRETCH BAR	3/16"x3/4" FLAT	3/16"x3/4" FLAT
GATE POST	3-1/2"	4.000"
TOP RAIL	1-1/4"	1.666"

7. CONSTRUCTION AND MATERIALS SHALL CONFORM TO SECT. 420 AND 722, RESPECTIVELY. SEE TABLE 722 FOR HEIGHTS OF MEMBERS.
8. ALL POSTS, RAILS, CHAIN LINK FABRIC, AND FASTENERS SHALL BE GREEN TO MATCH EXISTING.



CALL TWO WORKING DAYS BEFORE YOU DIG  
1-800-STAKE-IT

REVISIONS			
NO.	DESCRIPTION	DATE	BY

**SWI**  
Shephard Wesnitzer, Inc.












75 Kollof Place  
Sedona, AZ 86336  
928.282.1061  
928.282.2058 fax  
www.swiaz.com

JOB NO: 11311  
DATE: NOV 12  
SCALE: 1"=10'  
DRAWN: MWJ  
DESIGN: AHB  
CHECKED: AHB

POSSE GROUNDS PARK IMPROVEMENTS  
SEDONA ARIZONA

Professional Engineer  
ARTHUR H. BECKWITH  
11/07/12  
ARIZONA, USA  
Expires 3/31/2015

DRAWING NO. C3  
SHT NO. 3 OF 9



CALL TWO WORKING DAYS BEFORE YOU DIG  
1-800-STAKE-IT

REVISIONS			
NO.	DESCRIPTION	DATE	BY

**SWI**  
Shephard Wesnitzer, Inc.  
www.swiaz.com

75 Kollof Place  
Sedona, AZ 86336  
928.282.1061  
928.282.2058 fax

JOB NO:	11311
DATE:	NOV 12
SCALE:	1"=10'
DRAWN:	MWJ
DESIGN:	AHB
CHECKED:	AHB

POSSE GROUNDS PARK IMPROVEMENTS  
SEDONA ARIZONA

**DETAILS**

DRAWING NO. **C4**  
SHT NO. 4 OF 9

Professional Engineer  
ARTHUR H. BECKWITH  
11/07/12  
ARIZONA, USA  
Expires 3/31/2015


PLOTTED: Nov 07, 2012 - 11:16am

FILE: P:\2011\1311\Drawings\Construction\Plans\C5-SOCCER FIELD-1131.dwg MWJ-C3012

CURVE TABLE					
CURVE #	LENGTH	RADIUS	DELTA	CHORD DIRECTION	CHORD LENGTH
C1	8.44	7.50	Δ=64°29'33"	S 12°24'24" W	8.00
C2	12.19	12.50	Δ=55°51'51"	S 8°05'33" W	11.71
C3	19.27	202.50	Δ=5°27'04"	S 40°29'12" W	19.26

SURVEY CONTROL POINT TABLE				
POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
1	49624.77	53834.90	4535.06	FIELD CORNER
2	49598.44	53861.59	4534.74	END UNDERDRAIN
3	49545.77	53914.99	4534.10	END UNDERDRAIN
4	49519.44	53941.69	4533.78	FIELD MIDPOINT
5	49493.10	53968.39	4533.47	END UNDERDRAIN
6	49440.44	54021.79	4532.83	END UNDERDRAIN
7	49414.10	54048.48	4532.51	FIELD CORNER
8	49517.37	53782.23	4534.59	FIELD MIDPOINT
9	49466.04	53889.02	4533.31	CENTER OF FIELD
10	49360.71	53995.82	4531.76	FIELD MIDPOINT
11	49517.97	53729.56	4534.11	FIELD CORNER
12	49488.08	53752.75	4533.40	CATCH BASIN
13	49435.42	53806.15	4532.50	CATCH BASIN
14	49412.64	53836.36	4532.56	FIELD MIDPOINT

SURVEY CONTROL POINT TABLE				
POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
15	49382.75	53859.54	4531.77	CATCH BASIN
16	49330.08	53912.94	4530.94	CATCH BASIN
17	49307.31	53943.15	4531.01	FIELD CORNER
18	49274.70	53969.09	4529.60	MANHOLE
19	49468.51	53708.07	4534.82	BEGIN WALK
20	49484.40	53723.77	4534.66	PC
21	49492.22	53725.49	4534.66	PT
22	49511.53	53718.52	4534.24	PC
23	49523.13	53720.17	4534.04	PT
24	49579.31	53761.03	4534.73	PC
25	49593.96	53773.53	4534.87	PT
26	49650.34	53823.16	4534.88	END WALK
27	49298.68	53944.78	4530.80	CATCH BASIN



KEYNOTES					
101	1	LS	CLEAR & GRUB INCLUDING REMOVE AND DISPOSE EXISTING TURF		
102	505	CY	EARTHWORK EXCAVATION (CUT)		
103	418	CY	EARTHWORK EMBANKMENT (FILL)		
104	670	CY	SAND IMPORT PER TECHNICAL SPECIFICATIONS		
105	6035	SY	TOPSOIL PLACEMENT & GRADING PER TECHNICAL SPECIFICATIONS		
106	6035	SY	INSTALL TURFGRASS SOD PER TECHNICAL SPECIFICATIONS		
107	361	LF	INSTALL 15" HDPE ADS N-12 ASTM F2736 (OR EQUAL) STORM DRAIN PIPE PER MAG STD 621		
108	5	EA	INSTALL 18" NYLOPLAST (OR EQUAL) IN-LINE DRAIN WITH GRATE PER MANUFACTURERS DETAILS		
109	1	EA	INSTALL 30" NYLOPLAST (OR EQUAL) DRAINAGE BASIN WITH SOLID LID STAMPED "STORM DRAIN" PER MANUFACTURERS DETAILS		
110	1	LS	REMOVE AND SALVAGE IRRIGATION HEADS		
111	1	LS	REPLACE AND ADJUST IRRIGATION HEADS TO FINISHED GRADE		
112	1	LS	REMOVE AND SALVAGE GOAL POSTS		
113	1	LS	REPLACE GOAL POSTS UPON COMPLETION OF GRADING		
114	1	LS	CONSTRUCT SHADE STRUCTURE PER TECHNICAL SPECIFICATIONS AND DETAIL 'L' ON DWG C3		
134	28	EA	REMOVE AND DISPOSE TREE AND STUMP		
136	1	LS	REMOVE AND DISPOSE EXISTING CMP		
142	2	EA	ADJUST EXISTING MANHOLE, CLEANOUT, OR VALVE BOX TO FINISH GRADE		
144	40	CY	INSTALL 1" CRUSHED RED ROCK (2" THICK)		
145	155	LF	REMOVE, SALVAGE, AND REPLACE FENCE AFTER GRADING		
146	716	SY	SUBGRADE PREPARATION FIELD PERIMETER		
ADDITIVE ALTERNATE 1 - DOG TRAINING AREA					
102A	80	CY	EARTHWORK EXCAVATION (CUT)		
103A	2	CY	EARTHWORK EMBANKMENT (FILL)		
105A	704	SY	SUBGRADE PREPARATION		
118A	1140	SF	CONSTRUCT COMPACTED DECOMPOSED GRANITE WITH BINDER WALKWAY PER DETAIL 'A' ON DWG C3		
130A	142	LF	INSTALL 6' HIGH CHAIN LINK FENCE PER DETAIL 'K' ON DWG C3		
131A	2	EA	INSTALL 3'x6' HIGH CHAIN LINK GATE PER DETAIL 'K' ON DWG C3		
132A	2	EA	INSTALL 6'x6' HIGH CHAIN LINK GATE PER DETAIL 'K' ON DWG C3		
140A	1	LS	CONSTRUCT RETENTION DITCH WITH 3/4" RED ROCK PER DETAIL 'F' ON DWG C4		
ADDITIVE ALTERNATE 2 - SIDEWALK, IRRIGATION & PIPING					
117B	1140	SF	CONSTRUCT "SEDONA RED" CONCRETE SIDEWALK PER DETAIL 'B' DWG C3		
139B	1	LS	REMOVE AND SALVAGE ALL SPRINKLER HEADS, VALVES AND VALVE BOXES AND GIVE TO CITY MAINTENANCE FOR FUTURE USE. CAP 4" IRRIGATION SERVICE MAIN (IN THE AREA OF THE PROPOSED DOG PARK) DURING THE SOCCER FIELD CONSTRUCTION PERIOD. CONTRACTOR OR THEIR SUB SHALL DESIGN (SHOP DRAWINGS REQUIRED) AND INSTALL A NEW IRRIGATION SYSTEM FOR THE NEW SOCCER FIELD USING HUNTER I-40 ROTORS. CONNECT NEW SYSTEM TO EXISTING 4", 90 PSI MAIN LINE LOCATED IN THE PROPOSED DOG TRAINING AREA. ALL CONTROL WIRES WOULD BE RUN TO THAT 4" PIPE CONNECTION POINT AND SPLICED TO THE EXISTING CONTROL WIRES OF THE EXISTING IRRIGATION TIMER. SPRINKLER ZONES SHALL BE DESIGNED TO ALLOW PLAY ON HALF OF THE FIELD WHILE THE OTHER HALF IS BEING WATERED. THE CONTRACTOR DESIGNING AND INSTALLING THE IRRIGATION SYSTEM SHALL HAVE AT LEAST 5 YEARS OF EXPERIENCE DESIGNING AND INSTALLING LARGE SCALE COMMERCIAL SYSTEMS. CONTRACTOR SHALL ALSO MAKE RECOMMENDATIONS FOR APPROVAL AND IMPLEMENTATION FOR A FERTILIZER TREATMENT FOR THE MORTAR SAND AND FOR PLACEMENT ON THE SOD AFTER PLANTING.		
141B	616	LF	INSTALL 4" PERFORATED FIELD UNDERDRAIN PIPE PER DETAIL 'H' ON DWG C3		

CALL TWO WORKING DAYS BEFORE YOU DIG  
1-800-STAKE-IT


REVISIONS			
NO.	DESCRIPTION	DATE	BY

**SWI**  
Shephard Wesnitzer, Inc.

75 Kollof Place  
Sedona, AZ 86336  
928.282.1061  
928.282.2058 fax  
www.swiaz.com

JOB NO: 11311  
DATE: NOV 12  
SCALE: 1"=20'  
DRAWN: MWJ  
DESIGN: AHB  
CHECKED: AHB

POSSE GROUNDS PARK IMPROVEMENTS  
SEDONA ARIZONA  
**OVERALL SITE PLAN AND FIELD SURVEY CONTROL**



DRAWING NO.  
**C5**  
SHT NO. OF  
5 9

11/16/07

FILE: P:\2011\1311\Drawings\Construction\Plans\06-PARKING & SIDEWALK SITE PLAN-1311.dwg MWJ-C3012

SCALE: 1" = 10'

KEYNOTES			
100	1	LS	CLEAR AND GRUB
102	36	CY	EARTHWORK EXCAVATION (CUT)
103	385	CY	EARTHWORK EMBANKMENT (FILL)
105	1503	SY	SUBGRADE PREPARATION
107	94	LF	INSTALL 15" HDPE ADS N-12 ASTM F2736 (OR EQUAL) STORM DRAIN PIPE PER MAG STD 621
115	499	SY	CONSTRUCT 3" THICK ASPHALT PAVEMENT PER TYPICAL SECTION 'D' SHOWN ON DWG C3
116	151	TON	CONSTRUCT 6" THICK AGGREGATE BASE COURSE PER TYPICAL SECTION 'D' SHOWN ON DWG C3
117	1752	SF	CONSTRUCT 'SEDONA RED' CONCRETE SIDEWALK PER DETAIL 'B' DWG C3
118	693	SF	CONSTRUCT COMPACTED DECOMPOSED GRANITE WITH BINDER WALKWAY PER DETAIL 'A' ON DWG C3
119	989	SF	CONSTRUCT 'SEDONA RED' CONCRETE PAVEMENT SECTION PER DETAIL 'C' DWG C3
120	76	SF	CONSTRUCT CMU BLOCK WALL COLOR AND TYPE TO MATCH EXISTING
121	686	SF	CONSTRUCT MSE WALL PER DETAIL 'F' ON DWG C3
122	80	SF	CONSTRUCT 'SEDONA RED' CONCRETE BENCH CAP ON WALL PER DETAIL 'J' ON DWG C3
123	35	SF	CONSTRUCT CONCRETE STEPS PER DETAIL 'D' ON DWG C4
124	16	LF	CONSTRUCT HANDRAILS ON BOTH SIDES TO MEET ADA REQUIREMENTS PER DETAIL 'D' ON DWG C4
125	2	EA	CONSTRUCT TYPE 'E' CATCH BASIN PER M.A.G. STD. DETAIL 535. INSTALL KRISTAR FLOGARD PLUS OR EQUIVALENT OIL/SAND SEPARATOR.
126	1	LS	CONSTRUCT RETENTION BASIN
128	8	CY	INSTALL D50=4", 8" THICK RED ROCK RIP RAP PER MAG STD 221
129	95	LF	INSTALL 4" PERFORATED DRAIN PIPE PER DETAIL 'G' ON DWG C3
133	2	EA	ADA SIGNAGE PER SEDONA LAND DEVELOP CODE 912.09 D (1 VAN ACCESSIBLE)
137	60	LF	2" WATER LINE STUBOUT FOR FUTURE USE.
138	1	EA	IRRIGATION BOX WITH 3 CONTROL WIRES
143	59	LF	CONSTRUCT 2" VALLEY GUTTER PER DETAIL 'A' ON DWG C4
144	1	CY	INSTALL 1" CRUSHED RED ROCK (2" THICK)
147	1	LS	4" STRIPING PAVEMENT MARKING (WHITE)
148	1	LS	ADA PAVEMENT MARKING PER ADA REQUIREMENTS (WHITE)
149	15	EA	INSTALL CONCRETE WHEEL STOP PER DETAIL 'H' ON DWG C4
150	1	LS	INSTALL SECURITY FENCING (3' MIN HIGH ORANGE CAUTION FENCING STAKED AT 8' O.C.)
151	1	LS	REMOVE & DISPOSE EXISTING LANDSCAPE WOOD RETAINING WALL

ADDITIVE ALTERNATE			
102A	8	CY	EARTHWORK EXCAVATION (CUT)
103A	1	CY	EARTHWORK EMBANKMENT (FILL)
117A	-57	SF	CONSTRUCT 'SEDONA RED' CONCRETE SIDEWALK PER DETAIL 'B' DWG C3
117B	693	SF	CONSTRUCT 'SEDONA RED' CONCRETE SIDEWALK PER DETAIL 'B' DWG C3
121A	-19	SF	CONSTRUCT MSE WALL PER DETAIL 'F' ON DWG C3

REVISIONS			
NO.	DESCRIPTION	DATE	BY

**SWI**  
Shephard Wesnitzer, Inc.


75 Kollof Place  
Sedona, AZ 86336  
928.282.1061  
928.282.2058 fax  
www.swiaz.com

JOB NO: 11311  
DATE: NOV 12  
SCALE: 1"=10'  
DRAWN: MWJ  
DESIGN: AHB  
CHECKED: AHB



POSSE GROUNDS PARK IMPROVEMENTS

SEDONA ARIZONA

**PARKING AND SIDEWALK GRADING AND DRAINAGE PLAN**



DRAWING NO. **C6**  
SHT NO. 6 OF 9




FILE: P:\2011\1311\Drawings Construction Plans\C7-SURVEY CONTROL-11311.dwg MWJ-CSD12

1-800-STAKE-IT

SURVEY CONTROL POINT TABLE				
POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
1	49418.87	53789.95	4532.73	PI - MATCH EXISTING
2	49329.14	53890.70	4530.65	PI
3	49323.97	53889.92	4530.60	PI
4	49324.03	53889.42	4530.60	PI
5	49317.03	53888.59	4528.34	PC
6	49310.24	53897.49	4528.00	PT
7	49313.08	53904.46	4530.60	PI - TOP OF WALL
8	49311.47	53900.51	4529.20	PI - BENCH
9	49304.21	53908.36	4529.20	PI - BENCH
10	49300.30	53907.29	4527.58	PC
11	49293.91	53909.18	4527.37	PT
12	49273.12	53932.42	4526.12	PC
13	49272.66	53943.33	4527.50	PT - BENCH
14	49267.11	53954.71	4527.50	PI - BENCH
15	49263.40	53957.77	4526.21	PCC
16	49269.86	53967.16	4526.65	PI - END WALL
17	49270.43	53964.07	4529.60	PI - TOP WALL
18	49270.23	53970.20	4526.93	PCC
19	49280.60	53974.33	4527.50	PT
20	49286.74	53968.87	4527.50	PC
21	49293.72	53969.19	4527.50	PT - END WALL
22	49283.53	53978.94	4527.42	PC
23	49267.39	53979.17	4527.14	PCC
24	49257.46	53958.02	4526.04	PCC
25	49254.31	53947.64	4525.89	PCC
26	49252.64	53940.47	4525.78	PCC
27	49243.60	53900.76	4524.20	PI
28	49254.45	53899.27	4524.20	PI
29	49255.08	53917.52	4525.12	PCC
30	49257.01	53928.04	4525.66	PCC
31	49267.43	53931.32	4525.93	PT
32	49295.76	53899.67	4527.52	PC
33	49306.70	53876.51	4528.42	PT
34	49312.95	53835.91	4530.48	PC
35	49321.29	53825.17	4531.19	PT
36	49332.68	53820.29	4531.81	PI
37	49339.24	53812.81	4532.31	PI
38	49342.22	53815.47	4532.25	PI
39	49335.46	53822.84	4531.81	PI
40	49330.91	53830.04	4531.40	PI
41	49317.89	53836.67	4530.55	PT
42	49312.52	53871.59	4528.79	PC
43	49321.22	53883.04	4529.50	PT
44	49324.74	53883.46	4530.60	PI - TOP OF WALL
45	49324.80	53882.97	4530.60	PI - TOP OF WALL

SURVEY CONTROL POINT TABLE				
POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
46	49329.07	53883.31	4530.60	PI
47	49416.34	53786.40	4532.78	PI
48	49255.06	53990.59	4527.12	PI - PARKING LOT
49	49270.81	54015.79	4526.63	PC
50	49269.97	54022.11	4526.62	PT
51	49263.41	54028.18	4526.75	PI
52	49281.76	54047.99	4526.50	PI
53	49293.50	54037.12	4526.00	PI
54	49296.56	54040.42	4526.00	PI
55	49284.82	54051.29	4526.50	PI
56	49309.28	54077.70	4526.75	PI
57	49321.02	54066.83	4526.89	PI
58	49326.45	54072.70	4526.64	PI - MATCH EXISTING
59	49316.18	54082.21	4527.12	PI - TOP OF CONCRETE
60	49343.30	54051.83	4526.85	PI - MATCH EXISTING
61	49337.15	54046.72	4527.16	PI
62	49347.79	54033.92	4527.35	PI
63	49352.25	54041.07	4527.12	PI - TOP OF CONCRETE
64	49323.33	54007.51	4526.83	PI
65	49313.42	54016.68	4526.62	PC
66	49310.02	54013.01	4526.67	PT
67	49319.93	54003.84	4526.83	PI
68	49307.70	53990.64	4527.45	PI
69	49310.63	53987.92	4527.50	PI
70	49292.29	54004.90	4526.99	PI
71	49412.72	53803.85	4532.00	COLUMN CL
72	49404.58	53812.11	4532.00	COLUMN CL
73	49396.43	53820.37	4532.00	COLUMN CL
74	49388.28	53828.63	4532.00	COLUMN CL
75	49380.14	53836.89	4531.84	COLUMN CL
76	49259.06	53975.41	4527.12	BEGN WALL
77	49253.97	53986.45	4527.12	PCC
78	49252.75	53993.71	4527.12	PT
79	49261.26	54007.08	4527.12	END WALL
80	49264.03	54019.38	4527.12	BEGN WALL
81	49261.40	54021.81	4527.12	PC
82	49261.09	54030.82	4527.12	PT
83	49265.68	54035.66	4527.12	END WALL
84	49258.08	53940.10	4525.81	PCC
85	49260.98	53938.13	4525.85	PCC
86	49262.87	53938.31	4525.90	PCC
87	49265.21	53941.65	4525.95	PT
88	49263.72	53945.85	4525.96	PC
89	49258.99	53945.79	4525.97	PCC

CURVE TABLE					
CURVE #	LENGTH	RADIUS	DELTA	CHORD DIRECTION	CHORD LENGTH
C1	13.49	6.50	$\Delta=118^{\circ}57'01''$	S 52°41'15" E	11.20
C2	7.01	6.33	$\Delta=63^{\circ}26'17''$	S 16°27'15" E	6.66
C3	11.84	8.59	$\Delta=78^{\circ}55'24''$	S 87°38'05" E	10.92
C4	5.51	3.08	$\Delta=102^{\circ}19'11''$	N 39°26'46" W	4.80
C5	12.07	10.24	$\Delta=67^{\circ}30'23''$	S 55°38'27" W	11.38
C6	9.74	10.00	$\Delta=55^{\circ}48'20''$	N 82°09'45" E	9.36
C7	10.04	6.00	$\Delta=95^{\circ}49'14''$	N 61°8'24" E	8.91
C8	7.73	5.00	$\Delta=88^{\circ}34'52''$	N 23°38'39" E	6.98
C12	7.44	15.00	$\Delta=28^{\circ}24'12''$	N 76°54'41" E	7.36
C13	41.13	84.54	$\Delta=27^{\circ}52'30''$	S 77°03'32" W	40.72
C14	11.63	9.71	$\Delta=68^{\circ}37'19''$	S 75°01'0" E	10.95
C15	18.44	37.93	$\Delta=27^{\circ}51'29''$	N 88°01'16" E	18.26
C16	10.70	89.54	$\Delta=6^{\circ}50'49''$	S 79°39'14" W	10.69
C17	13.74	6.00	$\Delta=131^{\circ}15'02''$	N 17°27'08" E	10.93
C18	25.98	45.00	$\Delta=33^{\circ}04'25''$	N 64°42'36" W	25.62
C19	14.20	14.00	$\Delta=58^{\circ}06'00''$	S 52°11'48" E	13.60
C20	17.04	9.00	$\Delta=108^{\circ}28'43''$	S 27°00'27" E	14.61
C21	16.05	10.00	$\Delta=91^{\circ}57'57''$	N 52°46'14" E	14.38
C22	6.91	5.00	$\Delta=79^{\circ}12'51''$	N 82°24'34" W	6.38
C24	12.62	13.50	$\Delta=53^{\circ}32'24''$	N 65°13'43" W	12.16
C25	8.07	5.50	$\Delta=84^{\circ}01'58''$	N 80°28'31" W	7.36
C26	10.03	6.33	$\Delta=90^{\circ}46'18''$	S 88°03'30" E	9.02
C27	19.12	12.00	$\Delta=91^{\circ}16'15''$	N 24°59'9" E	17.16
C28	30.44	43.97	$\Delta=39^{\circ}39'40''$	S 28°47'24" W	29.83
C29	22.32	36.46	$\Delta=35^{\circ}04'18''$	N 66°00'15" E	21.97
C31	6.22	2.50	$\Delta=142^{\circ}34'38''$	N 04°53'8" E	4.74
C32	5.89	8.23	$\Delta=41^{\circ}00'24''$	N 80°52'59" E	5.76
C33	3.88	2.50	$\Delta=89^{\circ}00'36''$	S 34°06'31" E	3.50
C34	1.91	11.00	$\Delta=9^{\circ}56'13''$	S 52°54'1" E	1.91
C35	4.76	2.50	$\Delta=109^{\circ}00'45''$	S 54°57'57" W	4.07



CALL TWO WORKING DAYS BEFORE YOU DIG  
1-800-STAKE-IT

REVISIONS			
NO.	DESCRIPTION	DATE	BY

**SWI**  
Shephard Wesnitzer, Inc.  
75 Kollof Place  
Sedona, AZ 86336  
928.282.1061  
928.282.2058 fax  
www.swiaz.com

JOB NO:	11311
DATE:	NOV 12
SCALE:	1"=10'
DRAWN:	MWJ
DESIGN:	AHB
CHECKED:	AHB

POSSE GROUNDS PARK IMPROVEMENTS  
SEDONA ARIZONA  
**PARKING AND SIDEWALK SURVEY CONTROL**

SEDONA ARIZONA  
ARTHUR H. BECKWITH  
11/07/12  
Arizona, USA  
Expires 3/31/2015

DRAWING NO. **C7**  
SHT NO. 7 OF 9

FILE: P:\2011\1311\Drawings\Construction\Plans\SWPPP-01-1311.dwg MWJ-C3012

PLOTTED: Nov 07, 2012 - 11:17am



- LEGEND**
- STRAW WATTLE / STRAW WATTLE
  - DISTURBED AREA HATCHING (1.8± ACRES)
  - RIP RAP
  - INLET PROTECTION
  - DRAINAGE FLOW
  - BMP DETAIL SEE SWPPP SHEET 2
  - IP
  - TC (TRACK CONTROL)

STRAW WATTLES TO REMAIN IN PLACE UPON COMPLETION OF CONSTRUCTION

CALL TWO WORKING DAYS BEFORE YOU DIG  
1-800-STAKE-IT


REVISIONS			
NO.	DESCRIPTION	DATE	BY

**SWI**  
Shephard Wesnitzer, Inc.

75 Kollof Place  
Sedona, AZ 86336  
928.282.1061  
928.282.2058 fax  
www.swiaz.com

JOB NO:	11311
DATE:	NOV 12
SCALE:	1"=20'
DRAWN:	MWJ
DESIGN:	AHB
CHECKED:	AHB

POSSE GROUNDS PARK IMPROVEMENTS  
SEDONA ARIZONA  
**STORM WATER POLLUTION PREVENTION PLAN**



DRAWING NO.  
**S1**  
SHT NO. OF  
8 9



PLOTTED: Nov. 07, 2012 - 11:17am  
 FILE: P:\2011\1311\Drawings\Construction\Plans\SWPPP-02-11311.dwg  
 WML-C3D12  
 CALL TWO WORKING DAYS BEFORE YOU DIG  
 1-800-STAKE-IT





**A. EROSION & SEDIMENT CONTROL STANDARD NOTES**

1. THE CONTRACTOR MUST NOTIFY BLUE STAKE AT 1-800-STAKE-IT AT LEAST 24 HOURS PRIOR TO THE START OF CONSTRUCTION IN ACCORDANCE WITH APPLICABLE CITY ORDINANCES AND POLICIES.
2. THE CONTRACTOR GRANTS THE RIGHT-OF-ENTRY ON TO THIS PROPERTY TO THE DESIGNATED CITY OF SEDONA PERSONNEL FOR THE PURPOSE OF INSPECTING AND MONITORING FOR COMPLIANCE WITH EROSION AND SEDIMENT CONTROL LAW AND THE DESIGN AND CONSTRUCTION STANDARDS MANUAL.
3. ALL EROSION CONTROL MEASURES SHOWN ON THE APPROVED PLAN MUST BE IN PLACE, INSPECTED AND APPROVED BY THE CITY OF SEDONA PRIOR TO CLEARING, STRIPPING OF TOPSOIL OR GRADING.
4. THE CONTRACTOR SHALL POST A SIGN AT THE MAIN ENTRANCE TO THE CONSTRUCTION SITE CONTAINING THE AZPDES AUTHORIZATION NUMBER AND/OR COPY OF NOTICE OF INTEREST AUTHORIZATION, CONSTRUCTION SITE CONTACT NAME AND TELEPHONE NUMBER, A BRIEF PROJECT DESCRIPTION, AND THE LOCATION OF THE APPROVED STORM WATER POLLUTION PREVENTION PLAN. THE SIGN SHALL ALSO DISPLAY THE NAME, CONTACT INFORMATION, AND QUALIFICATIONS OF THE PERSONNEL PERFORMING ROUTINE INSPECTIONS.
5. THE CONTRACTOR'S REPRESENTATIVE IS RESPONSIBLE FOR THE INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION.
6. ALL DISTURBED AREAS ARE TO BE DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL COMPLETE AND ADEQUATE STABILIZATION IS ACHIEVED.
7. WATER MUST BE PUMPED INTO AN APPROVED FILTERING DEVICE DURING DEWATERING OPERATIONS.
8. THE CONTRACTOR'S REPRESENTATIVE SHALL INSPECT AND DOCUMENT ALL EROSION AND SEDIMENT CONTROL MEASURES DAILY AND AFTER EACH SIGNIFICANT RAINFALL. THE FOLLOWING ITEMS WILL BE CHECKED IN PARTICULAR:
  - A. SEDIMENT BASINS WILL BE CLEANED OUT WHEN THE LEVEL OF SEDIMENT BUILDUP REACHES THE CLEANOUT ELEVATION INDICATED ON THE RISER PIPE. SEDIMENT SHALL BE DISPOSED IN SUITABLE AREAS AND IN SUCH A MANNER THAT WILL NOT ERODE OR CAUSE SEDIMENTATION PROBLEMS. THE BASIN EMBANKMENT SHOULD BE CHECKED REGULARLY TO ENSURE THAT IT IS STRUCTURALLY SOUND AND HAS NOT BEEN DAMAGED BY EROSION OR CONSTRUCTION EQUIPMENT. EMERGENCY SPILLWAYS SHOULD BE CHECKED REGULARLY TO ENSURE THAT ITS LINING IS WELL ESTABLISHED AND EROSION RESISTANT.
  - B. SEDIMENT BASINS WILL BE CHECKED REGULARLY FOR SEDIMENT CLEANOUT. SEDIMENT SHALL BE REMOVED AND THE BASIN RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE HALF THE DESIGN VOLUME OF THE WET STORAGE. SEDIMENT REMOVED FROM THE BASIN SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE AND CAUSE SEDIMENTATION PROBLEMS.
  - C. GRAVEL OUTLETS WILL BE CHECKED REGULARLY FOR SEDIMENT BUILDUP WHICH WILL PREVENT DRAINAGE. IF THE GRAVEL IS CLOGGED BY SEDIMENT, IT SHALL BE REMOVED AND CLEANED OR REPLACED.
  - D. SILT FENCE BARRIERS WILL BE CHECKED REGULARLY FOR UNDERMINING OR DETERIORATION OF THE FABRIC. SEDIMENT SHALL BE REMOVED WHEN THE LEVEL OF SEDIMENT DEPOSITION REACHES HALF WAY TO THE TOP OF THE BARRIER.
  - E. SEEDED AREAS WILL BE CHECKED REGULARLY TO ENSURE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED AND RESEEDED AS NEEDED.
  - F. STREAM DIVERSION AND STORM CONVEYANCE CHANNELS SHALL BE INSPECTED DAILY AND AFTER EACH RAIN TO ENSURE THEY ARE FUNCTIONING PROPERLY AND THAT THE INTERIORS OF THE LININGS ARE NOT IMPAIRED. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES MUST BE MADE IMMEDIATELY AFTER THE INSPECTION.
9. INSPECTION FORMS SHALL BE COMPLETED BY THE CONTRACTOR'S INSPECTOR WITH THE MINIMUM FOLLOWING INFORMATION: INSPECTION DATE, TITLE AND QUALIFICATIONS OF EACH INSPECTOR, WEATHER INFORMATION FOR PERIOD SINCE LAST INSPECTION, LOCATION OF DISCHARGE OF SEDIMENT OR OTHER POLLUTANTS, LIST OF BMPs THAT NEED TO BE MAINTAINED OR ARE INADEQUATE, LIST ADDITIONAL NEEDED BMPs, CORRECTIVE ACTION REQUIRED, SOURCES OF ALL NON-STORMWATER AND CONTROL MEASURES, DATES WHEN MAJOR GRADING ACTIONS OCCURRED, POLLUTANT DISCHARGE STATUS OF STORAGE AREAS, AND DATES WHEN CONSTRUCTION ACTIVITIES CEASED.
10. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING INSPECTION RECORDS FOR AT LEAST THREE (3) YEARS FOLLOWING THE COMPLETION OF PROJECT. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE KEPT ON SITE AT ALL TIMES AND SHALL BE AMENDED AS NECESSARY TO REFLECT CURRENT SWPPP BMP'S.
11. THE SWPPP SHALL BE MODIFIED BY THE CONTRACTOR WITHIN 7 CALENDAR DAYS FOLLOWING AN INSPECTION THAT DISCOVERS AN INADEQUATE BMP. BMPs SHALL BE MODIFIED OR ADDED AS SOON AS PRACTICABLE AFTER THE BMP HAS BEEN DETERMINED INADEQUATE.
12. SEDIMENT BASIN MEASURES WILL BE INSTALLED AS A FIRST STEP IN GRADING AND WILL BE SEEDED AND MULCHED IMMEDIATELY FOLLOWING INSTALLATION.
13. PERMANENT SOIL STABILIZATION SHALL BE APPLIED TO DENUDED AREAS WITHIN SEVEN (7) DAYS AFTER FINAL GRADE IS REACHED AND ALL WORK COMPLETED ON ANY PORTION OF THE SITE. TEMPORARY SOIL STABILIZATION SHALL BE APPLIED WITHIN SEVEN (7) DAYS TO DENUDED AREAS THAT MAY NOT BE AT FINAL GRADE BUT WILL REMAIN UNDISTURBED FOR LONGER THAN FOURTEEN (14) DAYS. ROADS AND PARKING AREAS SHALL BE STABILIZED AS SOON AS PRECIPITATION OCCURS OR IRRIGATION IS AVAILABLE.
14. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES WILL BE REMOVED WITHIN 30 DAYS AFTER ADEQUATE SITE STABILIZATION AND AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED, AS AUTHORIZED BY THE CITY OF SEDONA INSPECTORS. TRAPPED SEDIMENT AND THE DISTURBED SOIL AREAS RESULTING FROM THE DISPOSITION OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED TO PREVENT FURTHER EROSION AND SEDIMENTATION.
15. WHEN SEDIMENT APPEARS ON A PAVED ROAD SURFACE, THE ROAD WILL BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT WILL BE REMOVED FROM THE ROADS BY SHOVELING OR SWEEPING AND TRANSPORTED TO A SEDIMENT CONTROL DISPOSAL AREA. STREET WASHING WILL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER.
16. AREAS WHICH ARE NOT TO BE DISTURBED WILL BE CLEARLY MARKED BY FLAGS, SIGNS, ETC.
17. A COPY OF THE PROJECT'S STORM WATER POLLUTION PREVENTION PLAN (SWPPP) SHALL BE MAINTAINED AT THE CONSTRUCTION SITE AND SHALL ALWAYS BE AVAILABLE FOR REVIEW.
18. CONTRACTOR SHALL BE RESPONSIBLE FOR UPDATING THE SWPPP THROUGHOUT CONSTRUCTION AND INDICATE ANY AND ALL REVISIONS / UPDATES ON THIS PLAN.
19. APPROVAL OF PLANS DOES NOT RELIEVE THE OPERATOR FROM CORRECTING ERRORS OR OMISSIONS DISCOVERED DURING CONSTRUCTION. CONFORMANCE WITH THE REQUIREMENTS OF THIS PLAN SHALL IN NO WAY RELIEVE THE OPERATOR FROM HIS RESPONSIBILITIES TO THE SITE AND ADJACENT PROPERTIES. TEMPORARY EROSION CONTROL SHALL CONSIST OF, BUT NOT BE LIMITED TO, CONSTRUCTING SUCH FACILITIES AND TAKING SUCH MEASURES AS ARE NECESSARY TO PREVENT, CONTROL AND ABATE WATER, MUD AND EROSION DAMAGE TO PUBLIC AND PRIVATE PROPERTY AS A RESULT OF THE CONSTRUCTION OF THIS PROPERTY.
20. CONTRACTOR SHALL IMMEDIATELY RESTORE ANY DAMAGED EROSION CONTROL MEASURE WITHIN THE PROJECT BOUNDARY.

21. FLOOD PLAIN LIMITS SHALL BE CLEARLY MARKED IN THE FIELD BY FLAGS, SIGNS, ETC.
  22. TREE SAVE AREAS SHALL BE CLEARLY MARKED IN THE FIELD BY ORANGE SAFETY FENCE.
  23. AN ORANGE SAFETY FENCE MUST BE INSTALLED AROUND ALL SILT TRAPS AND SEDIMENT BASINS.
  24. THE SWPPP SHALL BE MODIFIED BY THE CONTRACTOR WITHIN 15 BUSINESS DAYS FOLLOWING ANY CHANGE IN DESIGN, CONSTRUCTION OPERATION, OR MAINTENANCE THAT HAS A SIGNIFICANT EFFECT ON DISCHARGE OR NOT PREVIOUSLY ADDRESSED IN THE SWPPP.
  25. THE SWPPP SHALL BE MODIFIED BY THE CONTRACTOR WITHIN 15 BUSINESS DAYS IF IT IS DETERMINED THAT DISCHARGE IS CAUSING OR CONTRIBUTING TO WATER QUALITY EXCEEDENCES OR THE SWPPP IS INEFFECTIVE.
  26. ALL WORK IN ADJUT RIGHT OF WAY SHALL MEET THE REQUIREMENTS OF THE ADOT CONSTRUCTION PERMIT.
- B. EROSION CONTROL MEASURES**
- ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS ESTABLISHED HEREIN.
- C. STRUCTURAL PRACTICES**
1. SILT FENCE BARRIER: SILT FENCE SEDIMENT BARRIERS WILL BE INSTALLED DOWNSLOPE OF AREAS WITH MINIMAL GRADES TO FILTER SEDIMENT LADEN RUNOFF FROM SHEET FLOW AS INDICATED ON THE PLANS.
  2. A TEMPORARY CONSTRUCTION ENTRANCE SHALL BE INSTALLED WHERE THE ACCESS AREA INTERSECTS WITH EXISTING ROADS. DURING MUDDY CONDITIONS DRIVERS OF CONSTRUCTION VEHICLES WILL BE REQUIRED TO WASH THEIR WHEELS BEFORE ENTERING THE HIGHWAY.
  3. STORM DRAIN INLET & SPILLWAY PROTECTION: ALL STORM SEWER INLETS AND SPILLWAYS SHALL BE PROTECTED DURING CONSTRUCTION. SEDIMENT-LADEN WATER SHALL BE FILTERED BEFORE ENTERING THE STORM SEWER INLETS AND CULVERTS.
- D. VEGETATIVE PRACTICES**
1. TOP SOILING (STOCKPILE) TOPSOIL WILL BE STRIPPED FROM AREAS TO BE GRADED AND STOCKPILED FOR LATER USE. STOCKPILE LOCATIONS ARE TO BE STABILIZED WITH TEMPORARY VEGETATION. PRIOR TO LAND DISTURBING ACTIVITIES, THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION & SEDIMENT PLAN TO THE OWNER COVERING THE STOCKPILE AREA WHICH MAY HAVE TO BE APPROVED BY THE PLAN APPROVING AUTHORITY BEFORE ANY ACTIVITY COMMENCES.
  2. TEMPORARY SEEDING FOR ALL DENUDED AREAS WHICH WILL BE LEFT DORMANT FOR EXTENDED PERIODS OF TIME SHALL BE SEEDED WITH FAST GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING. SELECTION OF THE SEED MIXTURE WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED.
  3. EXISTING VEGETATION WILL BE PRESERVED OUTSIDE ALL LIMITS OF DISTURBANCE.
- E. MANAGEMENT STRATEGIES**
1. CONSTRUCTION WILL BE SEQUENCED SO THAT GRADING OPERATIONS CAN BEGIN AND END AS QUICKLY AS POSSIBLE.
  2. INSTALL TEMPORARY CONSTRUCTION ENTRANCE. MUD AND DEBRIS SHALL BE WASHED FROM ALL CONSTRUCTION VEHICLES AND EQUIPMENT BEFORE LEAVING THE SITE. A WATER TANK TRUCK WILL BE USED IF PUBLIC WATER IS UNAVAILABLE.
  3. INSTALL PERIMETER CONTROLS AS SHOWN TO INCLUDE DIVERSION DIKES, SILT FENCE, AND STRAW ROLLS. SEDIMENT TRAPPING MEASURES SHALL BE INSTALLED AS A FIRST STEP IN GRADING.
  4. GRADING OPERATIONS MAY COMMENCE ONCE PERIMETER CONTROLS, DIVERSIONS AND TRAPPING MEASURES ARE INSTALLED.
  5. FILL SLOPE SURFACES SHALL BE LEFT IN ROUGHENED CONDITION TO REDUCE SHEET AND RILL EROSION OF THE SLOPES. THE CONTRACTOR SHALL REDIRECT CONCENTRATED FLOW AWAY FROM THE FILL SLOPES BY INSTALLING EARTH BERMS AND DIRECT THE RUN-OFF TO STABILIZED OUTLET OR SEDIMENT BASIN AND TRAPPING DEVICES.
  6. TEMPORARY SEEDING OR OTHER STABILIZATION METHODS WILL FOLLOW IMMEDIATELY AFTER GRADING.
  7. ONCE THE UTILITIES, CURB AND GUTTER, AND THE ROADS ARE BROUGHT NEAR FINAL GRADE IN A MANNER SUCH THAT STORM SEWER SYSTEMS ARE FUNCTIONAL, INSTALL THE STANDARD INLET PROTECTION AROUND THE STRUCTURES.
  8. ONCE FINAL GRADES ARE ESTABLISHED TO CREATE SHEET FLOW CONDITIONS IN ACCORDANCE WITH REQUIRED DRAINAGE PATTERNS, THE CONTRACTOR MAY INSTALL SILT FENCE AND REMOVE EXISTING DIVERSION DIKES AND BASIN ALONG THE SITE PERIMETER WHEN AUTHORIZED BY THE INSPECTOR. INSTALL CHECK DAMS AND OUTLET PROTECTION AS SHOWN ON THE PLAN.
  9. FOR VEGETATIVE STABILIZATION OF ALL DENUDED AREAS SEE EROSION CONTROL MEASURES AND VEGETATIVE PRACTICES.
  10. THE JOB SUPERINTENDENT SHALL BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROL PRACTICES.
  11. AFTER ACHIEVING PERMANENT STABILIZATION, THE TEMPORARY EROSION & SILTATION CONTROLS WILL BE CLEANED UP AND REMOVED FROM THE SITE.
- F. MAINTENANCE**
- IN GENERAL, ALL EROSION & SEDIMENT CONTROL MEASURES WILL BE CHECKED DAILY AND AFTER EACH SIGNIFICANT RAINFALL.
- G. GENERAL LAND CONSERVATION NOTES**
1. VEGETATED STABILIZATION MEASURES MUST BE INITIATED AS SOON AS FINAL GRADING IS COMPLETE AND PRECIPITATION OCCURS OR IRRIGATION IS AVAILABLE.

2. ALL EROSION AND SILTATION CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN GRADING. THE FIRST AREAS TO BE CLEARED ARE TO BE THOSE REQUIRED FOR THE PERIMETER CONTROLS.
  3. ALL STORM AND SANITARY LINES NOT IN STREET ARE TO BE MULCHED AND SEEDED AS SOON AS PRECIPITATION OCCURS OR IRRIGATION IS AVAILABLE.
  4. ELECTRIC POWER, TELEPHONE, AND GAS SUPPLY TRENCHES ARE TO BE COMPACTED, SEEDED, AND MULCHED AS SOON AS PRECIPITATION OCCURS OR IRRIGATION IS AVAILABLE.
  5. DURING CONSTRUCTION, ALL STORM SEWER INLETS WILL BE PROTECTED BY INLET PROTECTION DEVICES, MAINTAINED AND MODIFIED AS REQUIRED BY CONSTRUCTION PROGRESS.
  6. ANY DISTURBED AREAS NOT PAVED, SODDED OR BUILT UPON ARE TO BE MULCHED WITH HAY OR STRAW MULCH AT THE RATE OF TWO TONS PER ACRE AND OVER-SEEDED AS SOON AS PRECIPITATION OR IRRIGATION IS AVAILABLE.
  7. AT THE COMPLETION OF CONSTRUCTION PROJECTS, AND PRIOR TO THE RELEASE OF THE BOND, ALL TEMPORARY SILTATION AND EROSION CONTROLS SHALL BE REMOVED AND DISTURBED AREAS SHALL BE STABILIZED.
  8. TEMPORARY DIVERSIONS, SILT FENCE, STRAW ROLL, STONE CONSTRUCTION ENTRANCE AND OTHER CONTROL MEASURES AS NECESSARY ARE TO BE PLACED AS INDICATED ON THE DRAWINGS PRIOR TO OR DURING THE FIRST STEP IN EXCAVATION.
  9. WHERE CONSISTENT WITH JOB SAFETY REQUIREMENTS, ALL EXCAVATED MATERIAL IS TO BE PLACED ON THE UPHILL SIDE OF TRENCHES. NO MATERIAL IS TO BE PLACED IN STREAMBEDS, WHERE SOIL IS PLACED ON DOWNHILL SIDE OF TRENCHES, IT IS TO BE BACK-SLOPED TO DRAIN TOWARD THE TRENCH. WHEN NECESSARY TO DEWATER THE TRENCHES, THE PUMP DISCHARGE HOSE MUST OUTLET IN A STABILIZED AREA.
- H. GENERAL NOTES**
1. ALL CONSTRUCTION SHALL CONFORM TO CITY OF SEDONA STANDARDS, MAG STANDARDS, YAG STANDARDS, AZPDES STANDARDS AND SPECIFICATIONS, AND GENERALLY ACCEPTED CONSTRUCTION PRACTICE.
  2. THESE PLANS REPRESENT A REASONABLE EFFORT TO IMPLEMENT THE MOST CURRENT AND BEST MANAGEMENT PRACTICES (BMPs) IN MITIGATING STORM WATER POLLUTION DURING CONSTRUCTION. THE EFFECTIVENESS OF THE MITIGATION MEASURES DEPICTED IN THESE PLANS DEPEND IN PART ON PROPER INSTALLATION, IMPLEMENTATION, MAINTENANCE AND REPAIR OF THE DEVICES SELECTED.
  3. THE DETAILS SHOWN ON THE DETAIL SHEET ARE BY SHEPARD - WESNITZER, INC. AND BY EROSION DRAW 4.0 (COPYRIGHT 2002 © JOHN MCULLAH) UNDER A LICENSE AGREEMENT.
  4. TOPOGRAPHIC AND BASE MAP INFORMATION (SHOWN FADING ON PLANS) PROVIDED BY COOPER AERIAL.
  5. SILT FENCE AND SLOPE TREATMENT LOCATIONS SHOWN ON BASE MAP FILES ARE APPROXIMATE. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING EXACT FILL SLOPE LOCATIONS AND PROVIDING SILT FENCE FOR ALL FILL SLOPES.

- I. SEEDING AND MULCHING**
- UNLESS OTHERWISE SPECIFIED IN THE CONSTRUCTION PLANS, ALL DISTURBED SLOPES SHALL BE MULCHED AND SEEDED PER THE FOLLOWING SEED SPECIFICATIONS:
- SEED SHALL BE OF VARIETY SPECIFIED, AND SHALL BE APPLIED AT THE RATE SPECIFIED.
- | SPECIES                                  | PURE LIVE SEED RATE/ACRE |
|--|--------------------------|
| SAND DRIPSEED (SPOROBOLUS CRYPTANDRUS)   | 2 LB                     |
| SIDEOLATS GRAMA (BOULELOUS CURTIPENDULA) | 10 LB                    |
| CRESTED WHEATGRASS (AGROPYRON CRISTATUM) | 10 LB                    |
1. SEEDING OPERATIONS SHALL NOT BE PERFORMED WHEN WIND WOULD PREVENT UNIFORM APPLICATION OF MATERIALS OR WOULD CARRY SEEDING MATERIALS INTO AREAS NOT DESIGNATED TO BE SEEDED.
  2. THE EQUIPMENT AND METHODS USED TO DISTRIBUTE SEEDING MATERIALS SHALL BE SUCH AS TO PROVIDE AN EVEN AND UNIFORM APPLICATION OF SEED, MULCH AND/OR OTHER MATERIALS AT THE SPECIFIED RATES.
  3. SEEDING OPERATIONS SHALL NOT BE PERFORMED ON UNDISTURBED SOIL OUTSIDE THE CLEARING AND GRUBBING LIMITS OF THE PROJECT OR ON STEEP ROCK CUTS.
  4. IMMEDIATELY BEFORE SEEDING, THE SURFACE AREA SHALL BE RAKED OR OTHERWISE LOOSENED TO OBTAIN A SMOOTH FRAGILE SURFACE FREE OF EARTH CLODS, HUMPS AND DEPRESSIONS. LOOSE STONES HAVING A DIMENSION GREATER THAN ONE INCH AND DEBRIS BROUGHT TO THE SURFACE DURING CULTIVATION SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR IN A MANNER APPROVED BY THE ENGINEER.
  5. THE AREA TO BE SEEDED SHALL BE ROUGHENED WITH GROOVES PARALLEL TO THE CONTOURS PRIOR TO SEEDING. A BULLDOZER OR CRAWLER TRACTOR SHALL BE DRIVEN UP AND DOWN THE SLOPE PARALLEL TO THE FALL LINE TO CREATE A TRACKWALKED SLOPE. THE SEEDS SHALL BE UNIFORMLY APPLIED IN A DIRECTION PARALLEL TO THE CONTOURS OF THE SLOPE. ALTERNATE SURFACE TREATMENT METHODS MAY BE APPROVED BY THE ENGINEER.
  6. IMMEDIATELY AFTER SEEDING, THE AREA SHALL BE UNIFORMLY COVERED WITH SCREENED MANURE AT THE RATE OF ONE CUBIC YARD PER 1,000 SQUARE FEET AND THEN WATERED UNTIL THE GROUND IS WET TO A MINIMUM DEPTH OF TWO INCHES.
  7. WATER SHALL BE FREE OF OIL, ACID, SALTS OR OTHER SUBSTANCES WHICH ARE HARMFUL TO PLANTS. THE SOURCE SHALL BE AS APPROVED BY THE ENGINEER PRIOR TO USE.
  8. THE CONTRACTOR SHALL PROTECT SEEDED AREAS FROM DAMAGE BY TRAFFIC OR CONSTRUCTION EQUIPMENT SURFACES WHICH ARE ERODED OR OTHERWISE DAMAGED FOLLOWING SEEDING AND PRIOR TO FINAL ACCEPTANCE SHALL BE REPAIRED BY REGRADEING, RESEEDED AND REMULCHED AS DIRECTED BY THE ENGINEER.



CALL TWO WORKING DAYS BEFORE YOU DIG  
1-800-STAKE-IT

REVISIONS				
NO.	DESCRIPTION	DATE	BY	

**SWI**  
Shephard Wesnitzer, Inc.

75 Kallof Place  
Sedona, AZ 86336  
928.282.1061  
928.282.2058 fax


www.swiaz.com

JOB NO:	11311
DATE:	NOV 12
SCALE:	
DRAWN:	
DESIGN:	
CHECKED:	

POSSE GROUNDS PARK IMPROVEMENTS

SEDONA ARIZONA

**STORM WATER POLLUTION PREVENTION PLAN**



DRAWING NO.	S2
SHT NO.	9
OF	9