



Date: 01/31/22 Author: STEPHEN MILLER Project: ST PATRICKS DAY PARADE, SEDONA
 Prime Contractor: CITY OF SEDONA Traffic Control Contractor: QUAIL CONSTRUCTION LLC

Comments:

- TRAFFIC CONTROL PLAN IS NOT TO SCALE
- THIS PLAN IS SUBJECT TO CHANGE IN THE FIELD
- ALL APPLICABLE EQUIPMENT SHALL HAVE SANDBAGS AND FLAGS
- BUSINESS AND LOCAL ACCESS SHALL BE MAINTAINED WHEN POSSIBLE
- CONFLICTING SIGNS SHALL BE COVERED WHILE TEMPORARY TRAFFIC CONTROL IS IN PLACE

TCP# 013122-006.2 SHEET #1

NOTES:
 SIGNS WILL HAVE FLAGS.
 28" REFLECTIVE CONES WILL BE USED FOR DAYTIME ONLY.
 28" REFLECTIVE CONES WILL BE SPACED AT 25' ON TAPERS & 40" ON TANGENTS.
 PARADE DATE: 03/12/22
 JORDAN ROAD CLOSURE HOURS: 1000-1400

SIGN SIZES		LEGEND
⊗ 18 X 24	○ 48 X 60	— PARADE ROUTE
○ 24 X 24	○ 48 X 96	●●● 28" REFLECTIVE CONES
○ 24 X 30	○ 30 X 48	↑ SIGN STAND
○ 30 X 30	○ 24 X 48	⚡ TYPE 3 BARRICADE
⊗ 36 X 36	○ 30 X 36	
⊗ 48 X 48	○ OTHER	

REVIEWED BY _____ DATE _____