



City of Sedona
Public Works Department
 102 Roadrunner Drive Sedona, AZ 86336
 (928) 204-7111 • Fax: (928) 282-5348

WW-14 - WWRP Area 4 Valve Vault Upgrade

FY24 CIP Update



KEY FEATURES:

Consultant: TBD

Contractor: TBD

Timing: FY24

Construction Challenges:

- Maintaining operation of area 4 pump station
- Isolation of water from reservoir

Project Manager:

Roxanne Holland, PE

(928) 203-5069

RHolland@SedonaAZ.gov

City Engineer:

Kurtis Harris, PE

(928) 203-5059

KHarris@SedonaAZ.gov

\$ FY24 Project Budget: \$140,000

Total Project Budget: \$140,000

Water level in the area 4 irrigation pump station is controlled by a custom fabricated motor operated slide gate that was originally installed in the 1990s. The slide gate has worn to a point that it will not close completely, resulting in water continually flowing into the overflow when pumps are not operating. If the slide gate is stuck in the open position, an offsite discharge would result in a permit violation and potential for flooding of downstream properties along Forest Service Road 525 exist. This project will replace the existing slide gate that provides level control to the area 4 pump station with a motor operated valve.

Status: Staff is reviewing a scope and fee proposal for design services. It is anticipated that design will commence in the fall of 2023 and be complete in spring 2024.

Project Status

November 2023

Project Phase	% Completion	Completion Date
Design	0%	Fall 2023
Construction	0%	Spring 2024